

**NORTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED**  
**OPERATION CIRCLE, ASIFABAD**  
TENDER NOTICE NO 02 /2018-19

Sealed Tenders are invited from registered contractors of TSNPDCL for execution of following work in operation circle, Asifabad.

1. Tender Notice No. : 02/2018-19 of SE/OP/ASF.
2. Specification No. : 05/2018-19

Sl No.	Speciation No.	Work description	Approximate Value of Work	Bid Security to be paid DD only	Cost of Specification
1	05/2018-19	Praposal for 33KV Inter linking line from 33/11 KVSS Penchikalpet on 33KV Penchikalpet feeder to arrange alternate power supply to 33/11 KVSS Chinnrajally and Other Sub-Stations on 33KV Dehagaom feeder in Dahegaon Section in Sirpur Kaghaznagar Division in Asifabad Circle. WBS No: T-1806-05-04-01-05-001	Rs.33,59,028.00	Rs.67,500.00	Rs.1000.00 Rs.0025.00 SGST Rs.0025.00 CGST Total Rs.1050.00 (Rs. 100.00 extra if required by post)

**1. Prequalification of a Bidder: Eligibility Criteria**

- Technical Qualification** :
1. Should Have '**A**' Grade Licence ( Not Below The Voltage Level Of 33 Kv)
  2. Should Have **TSNPDCL Valid Registration/Sap Vendor** Number.
  3. Should have Experience in Erection of **33kv/11kv/6.3kv /LT Lines & DTRs**, Energy Meters Etc...(Experience & Performance Should Be Certified By Divisional Engineer/Opn.)

- Financial Qualification**
1. Should have achieved minimum Financial Turnover of Rs.17,00,000/- in execution of 33kv/11kv/6.3kv /LT Lines & DTRs Work in any **consecutive 12 months** in last five years period and the same shall be certified by the Divisional Engineer /Operation.

2. Should have **Pan Card**
3. Should have **Aadhar Card/Address proof**
4. Should have **GST Registration Number**

- General**
1. Minimum three bids are required to open the Tender
  2. Should Have **Labour License** in Form-VI Issued By Concerned Area Labour Commissioner/Officer For The No.Of. Labours For Which The Tenderer Will Be Engaged For The Work.
  3. Should Have **EPF** Registration Number

4. Should Submit **Income Tax Clearance Certificate /Income Tax Return Copy** Before First Billing Failing Which The Bill Will Not Be Released

5. Bid Security will be forfeited if the bidder do not turn up for agreement with in 15 Days from the date of issue of Letter of Acceptance

**II. Other conditions:**

i). The Contractor shall be from same district/Local Area.

**III. Evaluation of Bids:**

i). If more than three bidders quotes same price (i.e. L1 price) the successful bidder will be decided through **Negotiations**, even then the bid will be finalized through **Lottery** and as per discretion of Management.

**IV. Contractor Overheads and profit including Labour Importation**

i) The allowable Contractor Overheads and profit including Labour Importation charges shall not be more than **+5.0 % To -10%**

ii) The security deposit shall be paid in the form of Demand Draft which will be deposited in the account of utility. No interest shall be payable on such amount by utility to bidder.


**V). Tender Schedule of Rates:**

- i) **Labour Portion:** As per the Circle Standard Schedule of Rates (SSR) to be adopted.
- ii) **Material portion:** As per the SAP prices to be adopted

The important dates of tender are

- 1). Sale of tender schedules : From **14** -11-2018 10:30Hrs  
: To **28** -11-2018 17:00Hrs
- 2). Submission of Sealed Tenders : Up to 13:00 Hrs on **29** -11-2018.
- 3). Opening of tender schedules : At 16:00 Hrs on **29** -11-2018.

The tender schedules are to be purchased on above date at O/o. Superintending Engineer, Operation Circle/TSNPDC/Asifabad during the office hours in working days duly paying the tender schedule cost of Rs.1050/- (Inclusive of GST) in shape of Demand Draft in favour of Superintending Engineer/Operation Circle/TSNPDC/ Asifabad payable at Asifabad.

  
SUPERINTENDING ENGINEER,  
OPERATION CIRCLE, ASIFABAD.



NORTHERN POWER DISTRIBUTION COMPANY OF T.S. LTD

SCHEDULE


Tender Notice No. 02/2018-19

Specification No. 05 /2018-19

Name of the work : Proposal for 33KV Inter linking line from 33/11 KVSS Penchikalpet on 33KV Penchikalpet feeder to arrange alternate power supply to 33/11 KVSS Chinnrajally and Other Sub-Stations on 33KV Dehagaom feeder in Dahegaon Section in Sirpur Kaghaznagar Division in Asifabad Circle. WBS No: T-1806-05-04-01-05-001

Sl. No.	SWR Codes	Description of item	Qty.	Unit	Rate/Per	Amount (Rs.)
<b>LABOUR (11KV Line)</b>						
1	SWR01138	Detailed Survey and Peg Marking	12.2	KM	730.07	8,906.83
2	SWR10786	clearing of light jungle, tree clearance	25,000.00	M2	0.79	19,703.39
3	SWR01205	Excav. of Pits for Poles(0.9x0.9x2.4 Mts)	10	EA	1143.50	11,435.00
4	SWR10788	excavation of pits for 9.1MPSCC poles	236	EA	713.71	1,68,436.00
5	SWR10830	Excavation of pits for 8.0 M poles/Stays	90	EA	594.75	53,527.88
6	SWR18139	Erection of 11 M Pole	10	EA	3282.05	32,820.51
7	SWR11864	Erection of 9.1M PSCC Poles, fixing of c	228	EA	2294.64	5,23,178.85
8	SWR01211	Bullock pair with strong cart	150	EA	652.68	97,901.69
9	SWR10650	Erection of Stud pole	60	EA	1063.87	63,832.37
10	SWR10651	Fixing of 33 KV Stays	30	EA	498.83	14,964.92
11	SWR21889	Formation of 33KV cut points/V.F/DP	30	EA	1496.50	44,895.00
12	SWR11172	Stringing of 100Sq.mm AAA Condr. on pole	12.2	KM	8999.99	1,09,799.90
13	SWR01010	Erection of Earthing	12	EA	1200.00	14,400.00
14	SWR01234	Numbering of poles incl. cost of paint	246	EA	31.70	7,799.03
15	SWR12743	33 KV, 800A AB switch	2	EA	4499.76	8,999.53
16	SWR00174	Erection of DP Strct. with 9.1PSCC Poles	4	EA	6404.19	25,616.75
17	SWR21846	Mass concreting of 8.0M poles	15	EA	2105.07	31,576.02
18	SWR21847	Mass concreting of 9.1M poles	57	EA	2386.94	1,36,055.62
19	SWR10661	Concreting of Stay pits	30	EA	1361.30	40,838.90
20	SWR18107	Construction of M+6 tower including fabr	2	EA	79552.00	1,59,104.00
21	SWR11456	Labour & Transport of Material	1	EA	10000.00	10,000.00
22	SWR21848	Mass concreting of above 10M poles	3	EA	2592.07	7,776.20
23	SWR11076	15% Extra for agency area	0.15	AU	1591568.38	2,38,735.26
24	SSC00100	1% CESS on total labour	0.01	LS	1830303.63	18,303.04
<b>NON STOCK MATERIAL</b>						
25	NMSC1002	MS Channel -100 X 50 mm	1500	KM	41.53	62,288.14
26	NMSA1002	MS Angle -65 x 65 x 6 mm	500	KM	41.53	20,762.71
27	NVXA3001	33KV V-X Arm-1.53M-MSChannel 100X50X6mm	220	EA	1745.76	3,84,067.80
28	NBCL3001	33KV Back Clamps with MS Flat 75x8mm	260	EA	137.29	35,694.92
29	NGIP3001	33KV GI Pin	738	EA	133.05	98,191.53
30	NBAN0003	MS BOLTS & NUTS 16x100 mm (5/8X4").....	1000	KM	56.78	56,779.66
31	NABS3003	33KV 800A Double Break Isolator	2	EA	34030.51	68,061.02
32	NSCL1002	M.S. Stay Clamp Set - 50x6 mm-Ea 1.536Kg.	120	EA	71.19	8,542.37
33	NBRS3001	33KV Standard bracing set-Double X-arm	22	SER	3050.85	67,118.64
34	NMPS3001	M+6 tower with 2 section stubs- 2.379MT	2	EA	98260.17	1,96,520.34
<b>Sub Total :</b>						<b>28,46,633.79</b>
			1	EA	2,56,197.04	2,56,197.04
GST			1	EA	2,56,197.04	2,56,197.04
<b>Total :</b>						<b>33,59,027.87</b>
Or Say Rs.						<b>33,59,028.00</b>
<b>(Rupees Thirty Three Lakhs Fifty Nine Thousand Twenty Eight only)</b>						

Contractor

  
SUPERINTENDING ENGINEER,  
OPERATION CIRCLE, ASIFABAD