

NORTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED
OPERATION CIRCLE, ASIFABAD
TENDER NOTICE NO 02 /2019-20

Sealed Tenders are invited from registered contractors of TSNPDCL for execution of following work in operation circle, Asifabad.

1. Tender Notice No. : 02/2019-20 of SE/OP/ASF.
2. Specification No. : 07/2019-20

Sl No.	Speciation No.	Work description	Approximate Value of Work	Bid Security to be paid DD only	Cost of Specification
1	07/2019-20	Proposal for 33KV Inter linking line from 132/33 KVSS Asifabad to 33/11 kVSS Vankulam on 33 KV Rebbena feeder to arrange alternate power supply to 33/11 KVSS Vankulam and 33/11 KVSS Adharshanagar on SKZR Town feeder in Rebbena Section in Asifabad Sub-Division of Asifabad Division in KB-Asifabad Circle WBS No: T-1910-15-01-01-03-001	Rs.20,51,995.00	Rs.41,100.00	Rs.1000.00 Rs.0025.00 SGST Rs.0025.00 CGST Total Rs.1050.00 (Rs. 100.00 extra if required by post)

1. Prequalification of a Bidder: Eligibility Criteria

Technical Qualification :

1. Should Have 'A' Grade Licence
(Not Below The Voltage Level Of 33 Kv)
2. Should Have TSNPDCL Valid Registration/Sap Vendor Number.
3. Should have Experience in Erection of 33kv/11kv/6.3kv /LT Lines & DTRs, Energy Meters Etc...(Experience & Performance Should Be Certified By Divisional Engineer/Opn.)

Financial Qualification

1. Should have achieved minimum Financial Turnover of Rs.10,50,000/- in execution of 33kv/11kv/6.3kv /LT Lines & DTRs Work in any **consecutive 12 months** in last five years period and the same shall be certified by the Divisional Engineer /Operation.
2. Should have Pan Card
3. Should have Aadhar Card/Address proof
4. Should have GST Registration Number

General

1. Minimum three bids are required to open the Tender
2. Should Have **Labour License** in Form-VI Issued By Concerned Area Labour Commissioner/Officer For The No.Of. Labours For Which The Tenderer Will Be Engaged For The Work.
3. Should Have **EPF** Registration Number

4. Should Submit **Income Tax Clearance Certificate /Income Tax Return Copy** Before First Billing Failing Which The Bill Will Not Be Released

5. Bid Security will be forfeited if the bidder do not turn up for agreement with in 15 Days from the date of issue of Letter of Acceptance

II. Other conditions:

i). The Contractor shall be from same district/Local Area.

III. Evaluation of Bids:

i). If more than three bidders quotes same price (i.e. L1 price) the successful bidder will be decided through **Negotiations**, even then the bid will be finalized through **Lottery** and as per discretion of Management.

IV. Contractor Overheads and profit including Labour Importation

i) The allowable Contractor Overheads and profit including Labour Importation charges shall not be more than **+5.0 % To -10%**

ii) The security deposit shall be paid in the form of Demand Draft which will be deposited in the account of utility. No interest shall be payable on such amount by utility to bidder.

V. Tender Schedule of Rates:


i) **Labour Portion:** As per the Circle Standard Schedule of Rates (SSR) to be adopted.

ii) **Material portion:** As per the SAP prices to be adopted

The important dates of tender are

- | | | | |
|----------------------------------|---------|--------------|-------------|
| 1). Sale of tender schedules | : From | 20-06-2019 | 10:30Hrs |
| | : To | 27-06-2019 | 17:00Hrs |
| 2). Submission of Sealed Tenders | : Up to | 13:00 Hrs on | 28-06-2019. |
| 3). Opening of tender schedules | : At | 16:00 Hrs on | 28-06-2019. |

The tender schedules are to be purchased on above date at O/o. Superintending Engineer, Operation Circle/TSNPDC/Asifabad during the office hours in working days duly paying the tender schedule cost of Rs.1050/- (Inclusive of GST) in shape of Demand Draft in favour of Superintending Engineer/Operation Circle/TSNPDC/ Asifabad payable at Asifabad.


SUPERINTENDING ENGINEER,
OPERATION CIRCLE, ASIFABAD.

NORTHERN POWER DISTRIBUTION COMPANY OF T.S. LTD

SCHEDULE


Tender Notice No. 02/2019-20
Specification No. 07 /2019-20

Name of the work : Proposal for 33KV Inter linking line from 132/33 KVSS Asifabad to 33/11 kVSS Vankulam on 33 KV Rebbena feeder to arrange alternate power supply to 33/11 KVSS Vankulam and 33/11 KVSS Adharshanagar on SKZR Town feeder in Rebbena Section in Asifabad Sub-Division of Asifabad Division in KB-Asifabad Circle WBS No: T-1910-15-01-01-03-001.

Sl. No.	SWR Codes	Description of item	Qty.	Unit	Rate/Per	Amount (Rs.)
LABOUR (11KV Line)						
			6.3	KM	737.37	4,645.45
1	SWR01138	Detailed Survey and Peg Marking			1.50	22,500.00
2	SWR10572	Clearing of Sarkar Thumma including gross	15,000.00	M2	720.85	140,565.25
3	SWR21841	Excavation of pits for 9.1M poles	195	EA	600.69	42,048.64
4	SWR21840	Excavation of pits for 8.0M /stay pit	70	EA	505.24	4,041.90
5	SWR21873	Fix of 33kv T Raiser incl erectn of stud	8	EA	2317.58	451,929.03
6	SWR21863	Transport & Erectn of 9.1M Poles	195	EA	1074.51	42,980.34
7	SWR10650	Erection of Stud pole	40	EA	503.82	15,114.66
8	SWR21875	Fix of 33kv Stay set	30	EA	1511.47	9,068.80
9	SWR21889	Formation of 33KV cut points/V,F/DP	6	EA	9090.00	63,320.94
10	SWR21876	Paving &Stringing of Dog conductor/100SQ	6,966	KM	1212.00	6,060.00
11	SWR12356	Pipe earthing tower GI Pipe 75mm 1.75Mtr	5	EA	32.02	6,563.47
12	SWR01234	Numbering of poles incl. cost of paint	205	EA	4544.76	9,089.53
13	SWR21894	Pre & fix of 33kv EDDA double break AB	2	EA	6468.25	32,341.23
14	SWR21837	Erection of DP with 9.1M poles for meter	5	EA	2128.30	85,131.86
15	SWR21846	Mass concreting of 8.0M poles	40	EA	2410.81	120,540.68
16	SWR21847	Mass concreting of 9.1M poles	50	EA	1374.92	41,247.46
17	SWR21845	Concreting of Stay Pit	30	EA	9201.69	9,201.69
18	SWR11456	Labour & Transport of Material	1	EA	4545.00	2,999.70
19	SWR1328	Dismantling of 33KV line	0.66	KM	1109390.64	166,408.60
20	SWR11076	15% Extra for agency area	0.15	AU		
NON STOCK MATERIAL						
21	NMSC1002	MS Channel 100 x 50 mm	400	KG	41.53	16,610.17
22	NBCL3001	33KV Back Clamps with MS flat 75x8mm	204	EA	137.29	28,006.78
23	NSCL3002	33KV stay clamp with MS flat 75x8mm-0.88	60	SET	208.47	12,508.47
24	NSCL1002	M.S.Stay Clamp Set 50x6 mm-Ea 1.536Kg.	80	EA	71.19	5,694.92
25	NGY11001	11KV Guy Insulator (H1)	60	EA	39.83	2,389.83
26	NPIN3002	33KV Pin Insulator w/o GI pin	660	EA	347.46	229,322.03
27	NGIP3001	33KV GI Pin	660	EA	133.05	87,813.56
28	NSIN3002	33 KV Polymer string insulators (B&S)	90	EA	266.10	23,949.15
29	NTMP3001	33KV Metal parts (B&S)	90	SET	155.93	14,033.90
30	NBAN0003	MS BOLTS & NUTS 16x100 mm(5/8X4).....	500	KG	56.78	28,389.83
31	NHTR3001	33KV T Raiser 3.6M 100x50mm with SClamps	8	EA	1807.63	14,461.02
Sub Total :						1,738,978.89
GST						
SGS19%						156,508.10
CGS19%						156,508.10
Total :						2,051,995.09
Or Say Rs.						2,051,995.00

(Rupees Twenty Lakhs Fifty One Thousand Nine Hundred and Ninty Five only)

Contractor


SUPERINTENDING ENGINEER,
OPERATION CIRCLE, ASIFABAD